

AJSIM Industrial Services Pvt. Ltd.

Rag Office: 3927/3, Jawahar Colony, 60 Feet Road, NIT Faridabad, Haryana Works: Plot no 14-15, Sec 70, IWA Gali no 9, Mujeri Industrial area, Faridabad.

Ph. +91-8094405989, +91-9990898551

ajsim.services@gmail.com, www.ajsimindia.com

AJSIM/MKT/2022-23/167 May 04, 2022

To, M/S Jindal Aluuminium Bhiwadi

Kind Attention: MR. Satyam Paliwal ji MOB;- 9112728092

Subject: Your requirement of 3T Transfer Trolley

Dear Sir,

With reference to the site visit and discussions, regarding the above subjected requirement and thanks for the same.

As discussed we are herewith enclosing our most competitive techno commercial offer as per enclosed Annexure I, II, III for your consideration and order finalization.

Hope the offer is inline of your requirement.

Please feel free to contact us, for the further clarifications.

Thanking you & assuring you of our best & prompt services always.

With Regards,

For AJSIM INDUSTRIAL SERVICES PVT LTD

Ajeet Maurya MOB:-08094405989 AJSIM

AJSIM Industrial Services Pvt. Ltd.

Rag Office :- 3927/3, Jawahar Colony, 60 Feet Road, NIT Faridabad, Haryana Works:- Plot no 14-15, Sec 70, IWA Gali no 9, Mujeri Industrial area, Faridabad.

Ph. +91-8094405989, +91-9990898551

ajsim.services@gmail.com, www.ajsimindia.com

Annexure - I

TECHNICAL PARAMETER OF TRANSFER TROLLEY CAPACITY 3 TONS,

	Mai	n technical points:	witewides crepted Bid members Salvati
	1.	Type of crane	: Transfer Trolley
	2.	Location	: Indoor
7	3.	Class	: M8 (IV) as per IS:3177,IS:800 & IS:807
7	4.	Capacity	(:3T)
7	5.	Platform Size	: 3000 x 1500 MM.
	5.	Platform Type	:Chequired sheet
7	7.	Trolley travel	: 100.0 Mtr.
->		Rail to rail distance	: 1000 mm
フ	8.	Speed	: 20.0 mtr./min
\rightarrow	9.	Motors Cross Travel - Rated HP - Duty - Type - CDF	: BBL/MARATHAN/CROMTOMMake : 2.0 HP, Sq. Cage : S-4 duty : 150 starts/hr, inverter duty, F-class, TEFC : 40%
~	10.	Gearbox casing	: Casting (AJSIM Make heavy duty)
-	11.	Operation	: By Pendent Push Button on wall / card Racho femple
~	12.	Limit Switches	: 1 No. Lever limit switch (2-way type) for CT
7	13.	Panels	trolley mounted, dust proof and maintenance friendly, having MCB's, brake contactors, over load relay

AJSIM

AJSIM Industrial Services Pvt. Ltd.

Rag Office: - 3927/3, Jawahar Colony, 60 Feet Road, NIT Faridabad, Haryana Works :- Plot no 14-15, Sec 70, IWA Gali no 9, Mujeri Industrial area, Faridabad. Ph. +91-8094405989, +91-9990898551

ajsim.services@gmail.com, www.ajsimindia.com

: Multi Core, PVC Sheathed flexible type 14. Cables EHT Thruster type / DCEM Brake 15. Brakes : EN-9 (Forged alloy steel) Wheel material 16. - CT size & nos. $: \phi 200, 04 \text{ nos.}$ 17. : 415V±10%, 3-phase, 50Hz Power supply : Through cable, CRD System spring type 19. Power supply : 45 Lbs/Yard rai (Client scope) 20. Rail 22. Trolley weight : 2.5T Approx

COMERCIAL TERMS AND DETAIL

Annexure - II

S.NO.	DESCRIPTION	UNIT PRICE	TOTAL	TOTAL
		(In Rs.)	QTY.	PRICE (In
				Rs.)
1.	Basic Prize for supply	5,81,000	1 No.	5,81,000
	Transfer trolley with	al		
	electrical.	200		
2.	Transport	280	M	30000
3.	Erection and	100		15000
	commissioning			
4.	CRD (SPRING TYPE)		1	65000
		TOTAL BASIC		6,91,000
		VALUE		6

Terms & Conditions

1. Prices:-The above prices are on Ex-works, Pandabad basis.

Le and Comerica jos; 2. <u>Taxes & Duties</u>:- All taxes and duties shall be charged extra as applicable at the time of dispatch.

AJSIM

AJSIM Industrial Services Pvt. Ltd.

Rag Office: - 3927/3, Jawahar Colony, 60 Feet Road, NIT Faridabad, Haryana Works: - Plot no 14-15, Sec 70, IWA Gali no 9, Mujeri Industrial area, Faridabad.

Ph. +91-8094405989, +91-9990898551

ajsim.services@gmail.com, www.ajsimindia.com

GST - 18%

- 3. **Packing & Forwarding**: We shall charge you 2% packing & forwarding.
- 4. <u>Freight:</u> Freight and Transit insurance shall be charged extra at actual at the time of dispatch.
- 5. <u>Delivery:</u> 6-7 weeks from the date of receipt of your purchase order and approved G.A. Drawing.
- 6. <u>Payment Terms:</u> 50% advance along with your P.O. and 40% against delivery and 10% after testing at site.
- 7. **Warranty**: Warranty of material will be 18 Months from the date of dispatch Or 12 Months from the date of commissioning.